

## Material Usage Report for: JONES RESIDENCE

CUSTOMER: DETEC SOLUTIONS  
LOCATION: 1249 MAPLE AVE  
GREENVILLE, SC 29601

ESTIMATOR: DAN KUKOL  
SALESPERSON: TREVOR HARLOW



Part Number	Quantity	Item Description	Unit of Measure	Item Usage
<b>FOOTINGS &amp; FOUNDATION</b>				
LAL8	6	4" LALLY COLUMN 8'	EACH	POSTS
LALCAP	6	4" COLUMN CAP OR BASE	EACH	POSTS
<b>BASEMENT &amp; SILLS</b>				
2416T	3	2X4X16' SYP TREATED #1 PREMIER	PC	WALL PLATE
2418F	3	2 X 4 X 18 DOUGLAS FIR	PC	WALL PLATE
2420F	3	2 X 4 X 20 DOUGLAS FIR	PC	WALL PLATE
2616T	3	2X6X16' SYP TREATED #1 PREMIER	PC	WALL PLATE
2618F	3	2 X 6 X 18 DOUGLAS FIR	PC	WALL PLATE
2620F	3	2 X 6 X 20 DOUGLAS FIR	PC	WALL PLATE
21216F	4	2 X 12 X 16 DOUGLAS FIR	PC	STAIR STRINGER
2478F	39	2 X 4 X 92-5/8" DOUGLAS FIR KD	PC	WALL STUDS
2678F	34	2 X 6 X 92-5/8" DOUGLAS FIR KD	PC	WALL STUDS
<b>1ST FLOOR DECK</b>				
PL400VQ	20	PL400 SUBFLOOR ADHESIVE VOC 280Z	EACH	SUBFLOOR ADHESIVE
11I360	656	11-7/8" PRO 360 TRUS JOIST	LNFT ( Tally: 12/12, 32/16; )	FLOOR JOISTS
11I560	528	11-7/8" PRO 560 TRUS JOIST	LNFT ( Tally: 22/24; )	FLOOR JOISTS

Part Number	Quantity	Item Description	Unit of Measure	Item Usage
11TS	13	1-1/4 X 11-7/8 TIMBERSTRAND 16'	PC	RIM JOISTS
2616T	13	2X6X16' SYP TREATED #1 PREMIER	PC	SILL
DOWSS	4	DOW SILL SEAL 1/4"X 5-1/2"X 50'	ROLL	SILL
34ADV	63	3/4" ADVANTECH T&G U/L 4X8	EACH	SUBFLOOR
<b>1ST FLOOR EXT WALLS</b>				
2616F	11	2 X 6 X 16 DOUGLAS FIR	PC	BLOCKING
21014F	14	2 X 10 X 14 DOUGLAS FIR	PC	HEADERS
2618F	14	2 X 6 X 18 DOUGLAS FIR	PC	WALL PLATE
2620F	14	2 X 6 X 20 DOUGLAS FIR	PC	WALL PLATE
269F	180	2 X 6 X 104-5/8" DOUGLAS FIR KD	PC	WALL STUDS
ZIPWALL	52	7/16" ZIP WALL SHTG.4X8 (GREEN)	EACH	WALL SHEATHING
ZTAPE	8	ZIP SYSTEM TAPE 3-3/4"x 90' ROLL	EACH	WALL SHEATHING
<b>1ST FLOOR INT WALLS</b>				
2418F	10	2 X 4 X 18 DOUGLAS FIR	PC	WALL PLATE
2420F	10	2 X 4 X 20 DOUGLAS FIR	PC	WALL PLATE
2618F	10	2 X 6 X 18 DOUGLAS FIR	PC	WALL PLATE
2620F	10	2 X 6 X 20 DOUGLAS FIR	PC	WALL PLATE
249F	120	2 X 4 X 104-5/8" DOUGLAS FIR KD	PC	WALL STUDS
269F	111	2 X 6 X 104-5/8" DOUGLAS FIR KD	PC	WALL STUDS
<b>GARAGE EXT WALLS</b>				
2618F	4	2 X 6 X 18 DOUGLAS FIR	PC	WALL PLATE
2620F	4	2 X 6 X 20 DOUGLAS FIR	PC	WALL PLATE
2610PC	60	2 X 6 X 116-5/8" DOUGLAS FIR KD	PC	WALL STUDS
ZIPWALL	20	7/16" ZIP WALL SHTG.4X8 (GREEN)	EACH	WALL SHEATHING
ZTAPE	4	ZIP SYSTEM TAPE 3-3/4"x 90' ROLL	EACH	WALL SHEATHING
<b>1ST FLOOR CEILING JOISTS</b>				

Part Number	Quantity	Item Description	Unit of Measure	Item Usage
21012F	3	2 X 10 X 12 DOUGLAS FIR	PC	BEAMS/GIRDERS
21012F	13	2 X 10 X 12 DOUGLAS FIR	PC	CEILING JOISTS
21016F	9	2 X 10 X 16 DOUGLAS FIR	PC	CEILING JOISTS
<b>2ND FLOOR DECK</b>				
PL400VQ	16	PL400 SUBFLOOR ADHESIVE VOC 280Z	EACH	SUBFLOOR ADHESIVE
11I360	804	11-7/8" PRO 360 TRUS JOIST	LNFT <i>( Tally: 8/12, 6/14, 12/16, 18/24; )</i>	FLOOR JOISTS
11TS	13	1-1/4 X 11-7/8 TIMBERSTRAND 16'	PC	RIM JOISTS
34ADV	49	3/4" ADVANTECH T&G U/L 4X8	EACH	SUBFLOOR
<b>2ND FLOOR EXT WALLS</b>				
21014F	4	2 X 10 X 14 DOUGLAS FIR	PC	HEADERS
2618F	13	2 X 6 X 18 DOUGLAS FIR	PC	WALL PLATE
2620F	13	2 X 6 X 20 DOUGLAS FIR	PC	WALL PLATE
2610PC	15	2 X 6 X 116-5/8" DOUGLAS FIR KD	PC	WALL STUDS
2678F	120	2 X 6 X 92-5/8" DOUGLAS FIR KD	PC	WALL STUDS
ZIPWALL	37	7/16" ZIP WALL SHTG.4X8 (GREEN)	EACH	WALL SHEATHING
ZTAPE	8	ZIP SYSTEM TAPE 3-3/4"x 90' ROLL	EACH	WALL SHEATHING
<b>2ND FLOOR INT WALLS</b>				
21014F	3	2 X 10 X 14 DOUGLAS FIR	PC	HEADERS
2418F	9	2 X 4 X 18 DOUGLAS FIR	PC	WALL PLATE
2420F	9	2 X 4 X 20 DOUGLAS FIR	PC	WALL PLATE
2618F	4	2 X 6 X 18 DOUGLAS FIR	PC	WALL PLATE
2620F	4	2 X 6 X 20 DOUGLAS FIR	PC	WALL PLATE
2478F	96	2 X 4 X 92-5/8" DOUGLAS FIR KD	PC	WALL STUDS
2678F	36	2 X 6 X 92-5/8" DOUGLAS FIR KD	PC	WALL STUDS
<b>2ND FLOOR CEILING JOISTS</b>				

Part Number	Quantity	Item Description	Unit of Measure	Item Usage
2812F	19	2 X 8 X 12 DOUGLAS FIR	PC	CEILING JOISTS
2816F	19	2 X 8 X 16 DOUGLAS FIR	PC	CEILING JOISTS
288F	13	2 X 8 X 8 DOUGLAS FIR	PC	CEILING JOISTS
<b>ROOF FRAMING &amp; SHEATHING</b>				
2616F	23	2 X 6 X 16 DOUGLAS FIR	PC	GABLE END FRAMING
ZIPWALL	8	7/16" ZIP WALL SHTG.4X8 (GREEN)	EACH	GABLE END FRAMING
ZTAPE	2	ZIP SYSTEM TAPE 3-3/4"x 90' ROLL	EACH	GABLE END FRAMING
11ML	96	11-7/8" MICRO LAM BEAMS	LNFT <i>( Tally: 4/24; )</i>	HIPS & VALLEYS
21012F	30	2 X 10 X 12 DOUGLAS FIR	PC	RAFTERS
21014F	20	2 X 10 X 14 DOUGLAS FIR	PC	RAFTERS
21016F	24	2 X 10 X 16 DOUGLAS FIR	PC	RAFTERS
21018F	27	2 X 10 X 18 DOUGLAS FIR	PC	RAFTERS
11ML	96	11-7/8" MICRO LAM BEAMS	LNFT <i>( Tally: 3/16, 2/24; )</i>	RIDGE
ZIPROOF	115	1/2" ZIP ROOF/WALL SHTG 4X8 (BR)	EACH	ROOF SHEATHING
ZTAPE	18	ZIP SYSTEM TAPE 3-3/4"x 90' ROLL	EACH	ROOF SHEATHING
ASTEP8	44	6 X 8 ALUM STEP FLASHING	PC	ROOF SHINGLES
WDRIP	21	F5-1/2 3-1/4" WHITE DRIP EDGE	PC	ROOF SHINGLES
WRAKE	6	1-1/2" WHITE ALUM RAKE STRIP	EACH	ROOF SHINGLES
<b>ROOF COVERAGE</b>				
CRRV	3	CERT ROLL RIDGE VENT 28LF	ROLL	ROOF SHINGLES
LM30WW	107	LANDMARK WEATHER WOOD	BNDL	ROOF SHINGLES
SRWW	2	SHADOW RIDGE WEATHEREDWOOD 30LF	BNDL	ROOF SHINGLES
USTART	2	SWIFT START 116' LF (STARTER)	EACH	ROOF SHINGLES
WG	5	WINTERGUARD ICE & WATER 195sf	ROLL	ROOF SHINGLES
<b>SIDING &amp; EXTERIOR TRIM</b>				

Part Number	Quantity	Item Description	Unit of Measure	Item Usage
548PVC	11	5/4x8 (15/16x7/1/4) PVC TRIM 20'	PC	BAND TRIM
546PVC	11	5/4x6 (15/16x5-1/2) PVC TRIM 20'	PC	CORNER TRIM
WZDC	8	1-5/16"x10' DRIP CAP WHITE ALUM.	EACH	DRIP CAP
6HPAW	378	6.25" SM HARDIE PLK ARC WHT 12'	PC <i>1800 SF</i>	EXT SIDING
HCAULKAW	18	HARDIE ARCTIC WHT TITEBOND CAULK	EACH	EXT SIDING
HTUAW	2	HARDIE ARCTIC WHT TOUCH UP KIT	EACH	EXT SIDING
3MTAPE9	8	9"x 75'3M FLASHING TAPE (4)	ROLL	FLASHING
546PVC	5	5/4x6 (15/16x5-1/2) PVC TRIM 20'	PC	HEAD TRIM
AHS	121	PVC HISTORIC SUBSILL - LF	LNFT	SILL
544PVC	20	5/4x4 (15/16x3-1/2) PVC TRIM 20'	PC	WINDOW/DOOR TRIM
<b>HARDWARE</b>				
LUS28Z	24	LUS28Z 2X8 HANGER (50)	EACH	HARDWARE
LSCZ	4	LSCZ STAIR STRINGER CONNECTOR	EACH	STAIR STRINGER

### Plan Note:

DISCLAIMER: Any take-off services performed by Detec Solutions LLC are estimates only, not guaranteed quantities. Our take-off service is designed to assist customers with creating a rough material budget. No warranty is expressed or implied as to the completeness of this estimate.